

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES 1 6	
2. MODIFICATION NO.: 0002		3. EFFECTIVE DATE SEP 09, 2002	4. REQUISITION/PURCHASE REQ. NO. W81W3G-2035-7181		PROJECT NO. (If applicable)
6. ISSUED BY Department of the Army Baltimore District, Corps of Engineers Contracting Division P.O. Box 1715 Baltimore MD 21203-1715		CODE CA31	7. ADMINISTERED BY: Contracting Division, Contracts Branch CENAB-CT-C 10 S. Howard ST. Room 7000 Baltimore, MD 21203-1715		CODE E1P0100
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(x)	9A. AMENDMENT OF SOLICITATION NO. DACA31-02-R-0054	
			X	9B. DATED (SEE ITEM 11) AUG 20, 2002	
				10A. MODIFICATION OF CONTRACT/ ORDER NO.	
				10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers **is not extended.**

DATE OF RECEIPT OF PROPOSAL 4:00 PM, LOCAL TIME, SEP 19, 2002

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS,
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER No. ITEM 10A
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR43.103(b)
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: changes clause FAR 52.243.1
D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

**CHILD DEVELOPMENT CENTER EXPANSION
GLEN HAVEN ANNEX, WALTER REED ARMY MEDICAL CENTER,
SILVER SPRING, MARYLAND**

SEE THE FOLLOWING PAGES

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
_____ (signature of person authorized to sign)		BY _____ (Signature of Contracting Officer)	

AMENDMENT NO. 0002 TO ADVERTISED RFP DACA31-02-R-0054
EFFECTIVE SEPT 09, 2002

SPECIFICATIONS:

1. Section 01050: Delete paragraph 1.2.2, "Explorations."
2. Section 01050, Para 1.4.3: Delete Submittal Advance notice.
3. Section 01050, Para 1.12: Add: "According to the Special Circumstances letter, received 8 August 2002, per the Garrison Environmental Office (GEO), no asbestos containing materials (ACM) have been identified and no radon above the action level is present in Building 130. GEO has not identified any records addressing lead-based paint (LBP) and PCB."
4. Section 02230a: Delete paragraph 1.2, 1.3, and 1.4 and all subparagraphs. Clearing and grubbing will be lump sum.
5. Section 02770A, Para 1.2: Delete this paragraph as sidewalks will be a lump sum item.
6. Section 03300, Paragraph 1.1: Delete ASTM C 78 from list of references.
7. Section 03300, Paragraph 1.6.2.1: Delete "Concrete slabs on-grade shall have a 28-day flexural strength of 650 psi". Delete "Flexural strength shall be determined in accordance with ASTM C 78".
8. Section 03300, Paragraph 1.6.2.1.d: Delete "Evaluation of Concrete Compressive Strength. Compressive strength specimens (6 by 12 inch cylinders) shall be fabricated by the Contractor and laboratory cured in accordance with ASTM C 31 and tested in accordance with ASTM C 39. The strength of the concrete will be considered satisfactory so long as the average of all sets of three consecutive test results equals or exceeds the specified compressive strength f'c and no individual test result falls below the specified strength f'c by more than 500 psi. A "test" is defined as the average of two companion cylinders, or if only one cylinder is tested, the results of the single cylinder test. Additional analysis or testing, including taking cores and/or load tests may be required at the Contractor's expense when the strength of the concrete in the structure is considered potentially deficient."
9. Section 03300, Paragraph 1.7.2: Delete "Proportioning Studies for Flexural Strength Concrete: Trial design batches, mixture proportioning studies, and testing requirements shall conform to the requirements specified in paragraph Proportioning Studies for Normal Weight Concrete, except that proportions shall be based on flexural strength as determined by test specimens (beams) fabricated in accordance with ASTM C 192 and tested in accordance with ASTM C 78. Procedures given in ACI 211.1 shall be modified as necessary to accommodate flexural strength."

AMENDMENT NO. 0002 TO ADVERTISED RFP DACA31-02-R-0054
EFFECTIVE SEPT 09, 2002

10. Section 03300, Paragraph 1.7.4: Delete entire paragraph titled “Average Flexural Strength Required for Mixtures”.
11. Section 03300, Paragraph 3.1.3: Delete “A 2 inch layer of compacted, clean concrete sand (fine aggregate) shall be placed on top of the vapor barrier before placing concrete.” Delete “...or any covering sand” at the end of the paragraph.
12. Section 03300, Paragraph 3.13.2.a: Add the following after the second sentence: “One test for air content shall also be made on each truckload of concrete.”
13. Section 03300, Paragraph 3.13.2.c: Add the following after the first sentence: “One slump test shall also be made on each truckload of concrete.”
14. Section 03300, Paragraph 3.13.2.f: Revise the first sentence to read as follows: “At least one set of test specimens shall be made for compressive strength on each different concrete mixture placed during the day for each 50 cubic yards or portion thereof of that concrete mixture placed each day.” Also, delete “and ASTM C 78 for test beams” in the sixth sentence.
15. Section 10520: Add this Section to Part 3 of this specifications. “Portable Fire Extinguishers shall meet the standards of NFPA 10 and shall be UL or equal certified. The Fire Extinguisher capacity shall be type 4A-60B:C or similar. The extinguishers shall be in glass front semi recessed cabinets. Cabinet to be constructed of 16 gage cold rolled steel with min. 22 gage steel for tubs. Cabinets shall have a clear glass door and shall be lockable. All finishes to be baked enamel. Cabinet construction shall maintain the fire rating of the wall in which it is located. Contractor to provide mounting and other accessories as required for proper operation of the fire extinguisher and cabinet. The cabinet shall meet ADAAG. Contractor to provide submittal drawings including standard manufacturers catalog for owner selection of extinguishers and cabinets with all options. Submittal drawings shall show mounting locations, heights and details. Provide allowance for training of personnel at the CDCX, testing and recharging of extinguishers after providing training.”
16. Section 13850A, Para 2.7.1: Add “All fire alarm conduit shall be minimum 3/4”.”
17. Section 13850A, Para 2.7.2: Add “All fire alarm initiating wiring shall be separate conduit from the fire alarm indicating wiring.”
18. Section 13850A, Para 3.6: Delete “The training period for systems operation shall consist of 2 training days (4 hours per day) at least one week apart...”. Add, “The training period for systems operation shall be divided into two 4-hour training courses, separated by one week minimum...”

AMENDMENT NO. 0002 TO ADVERTISED RFP DACA31-02-R-0054
EFFECTIVE SEPT 09, 2002

DRAWINGS:

19. Sheet T-2: Revise the following Sheet Titles: A-7 to read “Building Sections and Details” in lieu of “Building Sections and Wall Sections.”
20. Sheet T-2: General Note #2 to read “Contracting Officer” instead of “Architect.”
21. Sheet C-1 thru C-4: Per initial assessment from Maryland Department of the Environment (MDE), bioretention pond shown is adequate. Final comments from MDE to be made available on 9/09/02 (Sept. 09 2002).
22. Sheet C-1 & C-2: General Note 2 on both sheets:
 - a. Revise note No. 2 to read “Walter Reed Army Medical Center (WRAMC) will relocate the existing transformer on the south west side of the building. Contractor will be responsible for replacement of the existing transformer on the northeast corner of the parking lot adjacent to Building 130. New transformer size shall be 7620 120/240 167 KVA single phase. This transformer will be placed on the existing pad at the existing location. All primary and secondary cables shall be reconnected to new transformer in addition to new secondary for new CDCX addition.”
 - b. Add note No. 3 to read “Contractor to demolish existing light pole as indicated. Disposal will be at Contractor’s expense and according to Specification Section 01572 and 02220a.”
 - c. Add note no. 4 to read “Relocation and upgrade of respective transformers and demolition of light pole will be coordinated with WRAMC DPW and be scheduled accordingly.”
23. Sheet A-1: Add General Note No. 1 to the Phasing Plan as follows: “Contractor to provide recommendations to the phasing plan on Sheet A-1 for review by the Contracting Officer. The phasing plan shall ensure the minimum amount of disruption to the functioning of the existing facility during construction. This includes the following:
 - a. Ensure that there are two means of egress from the building at all times when the children are present to meet fire codes.
 - b. Ensure that temporary heating and hot water is available during the period when the new system is being energized.”

AMENDMENT NO. 0002 TO ADVERTISED RFP DACA31-02-R-0054
EFFECTIVE SEPT 09, 2002

24. Sheet A-2: Add note "Floor finish in Vestibule 100 and Exterior Storage Room 124 to be sealed concrete in lieu of concrete."
25. Sheet A-1, A-2: Window behind reception desk to be "existing to remain".
26. Sheet A-6, Details 10/A6, 17/A6: Cabinets height for cabinets in Activity Room #2; Room No. 120 to be 30" high in lieu of 36". See detail 10/A6 and 17/A6. Contractor to provide 1 single bowl stainless steel hand washing sink and all required accessories and plumbing for the sink in this countertop. Locate sink as shown in 10/A6.
27. Sheets A-6, A-7 and A-8: Delete these sheets in their entirety as originally issued and substitute the attached like-numbered revised sheets, designated as Addendum #1 (this should read #2).
28. Sheet P-2: Add note "Contractor shall field coordinate exact routing of domestic water piping and gas piping from Mechanical Room, E-109, through P.M. Room, E108 to avoid running piping above the existing electrical panels on the adjoining walls of the two rooms."
29. Sheet P-2: Add note "Contractor to provide 1 single bowl stainless steel hand washing sink and all required accessories and plumbing for the sink in countertop on the north side of Activity Room 32, Room 120. Use specifications for hand washing sink in the kitchen."
30. Sheets E-2 and E-5: Delete these sheets in their entirety as originally issued and substitute the attached like-numbered revised sheets, designated as Addendum #1 (this should read #2).
31. Sheet E-3: Provide smoke detector in Staff Toilet 118, in lieu of heat detector.
32. Sheet E-3: Provide smoke detector in Office E107.
33. Sheet E-4: Revise "1P2CE" to be "1-POLE" in last sentence of Drawing Note 18.
34. Sheet E-4: Revise plan and Drawing Note 10 to terminate empty conduit in Storage E106, in lieu of PM Room E108.
35. Sheet E-4: All electrical outlets in North wall of Activity Room #2, Room 120, to be 42" AFF.
36. Sheet E-4: Add one additional electrical outlet in the north wall of Activity Room #2, Room 120, at 42" AFF.

AMENDMENT NO. 0002 TO ADVERTISED RFP DACA31-02-R-0054
EFFECTIVE SEPT 09, 2002

37. Sheet E-4: Add General Note #2 reading “Contractor shall provide all communications conduit, cabling, and jacks. Provide one 4-pair Category 5E cable from each jack and terminate at backboard. Each outlet location shall contain two jacks per the specifications. Conduit shall be provided from each outlet box to the nearest cable tray or backboard.”

ATTACHMENTS: Revised Sheets A-6, A-7, A-8, E-2 and E-5, designated as Addendum #1.