

AMENDMENT NO. 0007 TO RFP W912DR-04-S-0001
EFFECTIVE JUN 17, 2004

SPECIFICATIONS:

- 1) Table of Contents Page 1, DIVISION 02 – SITE CONSTRUCTION: Delete section numbers and titles as follows: “02510A WATER DISTRIBUTION SYSTEM,” “02531 SANITARY SEWERS,” and “02532A FORCE MAINS AND INVERTED SIPHONS; SEWERS”
- 2) Table of Contents Page 1, DIVISION 07 – THERMAL AND MOISTURE PROTECTION: Add section number and title as follows: “07611N STEEL STANDING SEAM ROOFING”.
- 3) Division 2: Delete SECTION 02510A WATER DISTRIBUTION SYSTEM, SECTION 02531 SANITARY SEWERS and SECTION 02532A FORCE MAINS AND INVERTED SIPHONS in their entirety.
- 4) Section 07611N STEEL STANDING SEAM ROOFING: Add attached Section 07611N, dated June 16, 2004, and attached corresponding submittal register.

DRAWINGS:

- 5) Plates 4 and 51: The correct number and locations of transformers/switchgear pads are as indicated on Plate 4, dated 6/7/04. Disregard the number and location of pads as shown on Plate 51, dated 6/9/04.
- 6) Plates 9 and 51: The correct number of conduits for various electrical duct banks is as indicated on Plate 9, dated 6/7/04. Disregard the number and location of pads as shown on Plate 51, dated 6/9/04.

ATTACHMENTS

- 1) Section 07611N “STEEL STANDING SEAM ROOFING.”
- 2) Section 07611N Submittal Register.

SECTION 07611N

STEEL STANDING SEAM ROOFING

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG-973 (1996) Cold-Formed Steel Design Manual

ASTM INTERNATIONAL (ASTM)

ASTM A 36/A 36M (2003a) Carbon Structural Steel

ASTM A 366/A 366M (1997e1) Commercial Steel, Sheet, Carbon, (0.15 Maximum Percent Cold-Rolled**

ASTM A 570/A 570M (1998) Steel, Sheet and Strip, Carbon, Hot-Rolled

ASTM A 607 (1998) Steel, Sheet and Strip, High-Strength, Low-Alloy, Columbium or Vanadium, or Both, Hot-Rolled and Cold-Rolled

ASTM A 653/A 653M (2003) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM A 792/A 792M (2002) Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process

ASTM B 117 (2002) Operating Salt Spray (Fog) Apparatus

ASTM D 1654 (1992; R 2000) Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments

ASTM D 2244 (2002e1) Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates

ASTM D 2247 (2002) Testing Water Resistance of Coatings in 100% Relative Humidity

ASTM D 4214 (1998) Evaluating the Degree of Chalking of Exterior Paint Films

ASTM D 522 (1993a; R 2001) Mandrel Bend Test of Attached Organic Coatings

ASTM D 523	(1989; R 1999) Specular Gloss
ASTM D 714	(2002) Evaluating Degree of Blistering of Paints
ASTM D 968	(1993; R 2001) Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM E 1592	(2001) Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference
ASTM E 84	(2003) Surface Burning Characteristics of Building Materials
ASTM G 23	(1996) Operating Light-Exposure Apparatus (Carbon-Arc Type) With and Without Water for Exposure of Nonmetallic Materials

SHEET METAL & AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION
(SMACNA)

SMACNA Arch. Manual	(1993; Errata; Addenda Oct 1997; 4th Printing 1999) Architectural Sheet Metal Manual
---------------------	--

1.2 DEFINITIONS

1.2.1 Field-Formed Seam

Seams of panels so configured that when adjacent sheets are installed the seam is sealed utilizing mechanical or hand seamers. Crimped (45 degree bend), roll formed (180 degree bend), double roll formed (2 - 180 degree bends), and roll and lock systems are types of field-formed seam systems.

1.2.2 Snap Together Seam

Panels so configured that the male and female portions of the seam interlock through the application of foot pressure or tamping with a mallet. Snap-on cap configurations are a type of snap together system.

1.2.3 Pre-Formed

Formed to the final, less field-formed seam, profile and configuration in the factory.

1.2.4 Field-Formed

Formed to the final, less field-formed seam, profile and configuration at the site of work prior to installation.

1.2.5 Roofing System

The roofing system is defined as the assembly of roofing components, including roofing panels, flashing, fasteners, and accessories which, when assembled properly result in a watertight installation.

1.3 SYSTEM DESCRIPTION

1.3.1 Design Requirements

- a. Panels shall be continuous lengths up to manufacturer's standard longest lengths, with no joints or seams, except where indicated or specified. Ribs of adjoining sheets shall be in continuous contact from eave to ridge. Individual panels of snap together type systems shall be removable for replacement of damaged material.
- b. There shall be no exposed or penetrating fasteners except where shown on approved shop drawings. Fasteners into steel shall be stainless steel, zinc cast head, or cadmium plated steel screws inserted into predrilled holes. There shall be a minimum of two fasteners per clip. Single fasteners will be allowed when supporting structural members are prepunched or predrilled.
- c. Snap together type systems shall have a capillary break and a positive side lap locking device. Field-formed seam type systems shall be mechanically locked closed by the manufacturer's locking tool. The seam shall include a continuous factory applied sealant when required by the manufacturer to withstand the wind loads specified.
- d. Roof panel anchor clips shall be concealed and designed to allow for longitudinal thermal movement of the panels, except where specific fixed points are indicated. Provide for lateral thermal movement in panel configuration or with clips designed for lateral and longitudinal movement.

1.3.2 Design Conditions

The system shall be designed to resist positive and negative loads specified herein in accordance with the AISI SG-973. Panels shall support walking loads without permanent distortion or telegraphing of the structural supports.

1.3.2.1 Wind Uplift

Installed roof system shall withstand negative (uplift) design wind loading pressures complying with the following criteria:

- a. Safety Factor: 1.875 after any load reduction or material stress increase.
- b. Category III Building with an Importance Factor of 1.15.
- c. Wind Speed: 100 mph.
- d. Ultimate Pullout Value: 400 pounds per each of the two fasteners holding the panel anchor to the roof decking or framing system.
- e. Exposure Category: C.
- f. Design Roof Height: 30 feet .
- g. Roof slope: Minimum of 1 to 12 to a maximum of 1 to 10: 10

Capacity shall be determined using pleated airbag method in accordance with ASTM E 1592, testing of sheet metal roof panels. Allowable safe working loads shall be determined by dividing the ultimate test load by the safety factor specified above

1.3.2.2 Roof Live Loads

a. The installed roof system shall be capable of resisting the following positive uniform roof loads: Roof Live Load of 20 psf; Roof Snow Load of 10 psf.

b. Capacity to resist positive loads shall be determined by empirical calculations in accordance with AISI. Calculation shall be sealed by a registered professional engineer.

1.3.2.3 Thermal Movement

System shall be capable of withstanding thermal movement based on a temperature range of 10 degrees F below zero degrees F and 140 degrees F.

1.3.2.4 Deflection

Panels shall be capable of supporting design loads between unsupported spans with deflection of not greater than L/180 of the span.

1.3.3 Structural Performance

The structural performance test methods and requirements of the Standing Seam Roofing Systems (SSRS) shall be in accordance with ASTM E 1592.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Roofing; G AE

Submit roofing drawings to supplement the instructions and diagrams. Drawings shall include design and erection drawings containing an isometric view of the roof showing the design uplift pressures and dimensions of edge, ridge and corner zones; and show typical and special conditions including flashings, materials and thickness, dimensions, fixing lines, anchoring methods, sealant locations, sealant tape locations, fastener layout, sizes, and spacing, terminations, penetrations, attachments, and provisions for thermal movement. Details of installation shall be in accordance with the manufacturer's Standard Instructions and details or the SMACNA Arch. Manual. Prior to submitting shop drawings, have drawings reviewed and approved by the manufacturer's technical engineering department.

SD-03 Product Data

Roofing panels; G AE

Attachment clips

Closures

Accessories

Fasteners

Sealants

Insulation, including joint sealing measures for vapor barrier facing]

Sample warranty certificate; G AE

Submit for materials to be provided. Submit data sufficient to indicate conformance to specified requirements.

SD-04 Samples

Roofing panel

Submit a 12 inch long by full width section of typical panel.

For color selection, submit 2 by 4 inch metal samples in color, finish and texture specified.

Accessories

Submit each type of accessory item used in the project including, but not limited to each type of anchor clip, closure, fastener, and leg clamp.

Sealants

Intermediate Support Section

Submit full size samples of each intermediate support section, 12 inches long.

SD-05 Design Data

Design calculations

SD-06 Test Reports

Field Inspection; G AE

Submit manufacturer's technical representative's field inspection reports as specified in paragraph entitled "Manufacturer's Field Inspection."

Structural performance tests

Finish tests

SD-07 Certificates

Manufacturer's Technical Representative's Qualifications

Statement of Installer's Qualifications

Submit documentation from roofing manufacturer proving the manufacturer's technical representative meets below specified requirements. Include name, address, telephone number, and experience record.

Submit documentation proving the installer is factory-trained, has the specified experience, and authorized by the manufacturer to install the products specified.

Coil stock compatibility; G AE

Provide certification of coil compatibility with roll forming machinery to be used for forming panels without warping, waviness, and rippling not part of panel profile; to be done without damage, abrasion or marking of finish coating.

SD-08 Manufacturer's Instructions

Installation manual; G AE

Submit manufacturers printed installation manual, instructions, and standard details.

SD-11 Closeout Submittals

Information card

For each roofing installation, submit a typewritten card or photoengraved aluminum card containing the information listed on Form 1 located at the end of this section.

1.5 DESIGN CALCULATIONS

Provide design calculations prepared by a professional engineer specializing in structural engineering verifying that system supplied and any additional framing meets design load criteria indicated. Coordinate calculations with manufacturer's test results. Include calculations for:

Wind load uplift design pressure at roof locations specified in paragraph entitled "Wind Uplift."

Clip spacing and allowable load per clip.

Fastening of clips to structure or intermediate supports.

Intermediate support spacing and framing and fastening to structure when required.

Allowable panel span at anchorage spacing indicated.

Safety factor used in design loading.

Governing code requirements or criteria.

Edge and termination details.

1.6 QUALITY ASSURANCE

1.6.1 Preroofing Conference

After submittals are received and approved but before roofing work, including associated work, is preformed, the Contracting Officer will hold a preroofing conference to review the following:

- a. The drawings and specifications
- b. Procedure for on site inspection and acceptance of the roofing substrate and pertinent structural details relating to the roofing system
- c. Contractor's plan for coordination of the work of the various trades involved in providing the roofing system and other components secured to the roofing
- d. Safety requirements

The preroofing conference shall be attended by the Contractor and personnel directly responsible for the roofing and insulation installation, mechanical and electrical work, and the roofing manufacturer's technical representative. Conflicts among those attending the preroofing conference shall be resolved and confirmed in writing before roofing work, including associated work, is begun. Prepare written minutes of the preroofing conference and submit to the Contracting Officer.

1.6.2 Manufacturer

The SSMRS shall be the product of a metal roofing industry - recognized manufacturer who has been in the practice of manufacturing SSMRS for a period of not less than 5 years and who has been involved in at least 5 projects similar in size and complexity to this project.

1.6.3 Manufacturer's Technical Representative

The representative shall have authorization from manufacturer to approve field changes and be thoroughly familiar with the products and with installations in the geographical area where construction will take place. The manufacturer's representative shall be an employee of the manufacturer with at least 5 years experience in installing the roof system. The representative shall be available to perform field inspections and attend meetings as required herein, and as requested by the Contracting Officer.

1.6.4 Installer's Qualifications

The roofing system installer shall be factory-trained, approved by the metal roofing system manufacturer to install the system, and shall have a minimum of three years experience as an approved applicator with that manufacturer. The applicator shall have applied five installations of similar size and scope as this project within the previous 3 years.

1.6.5 Single Source

Roofing panels, clips, closures, and other accessories shall be standard products of the same manufacturer; shall be the latest design by the manufacturer; and shall have been designed by the manufacturer to operate as a complete system for the intended use.

1.6.6 Laboratory Tests For Panel Finish

The term "appearance of base metal" refers to the metal coating on steel. Panels shall meet the following test requirements:

- a. Formability Test: When subjected to a 180 degree bend over a 1/8 inch diameter mandrel in accordance with ASTM D 522, exterior coating film shall show only slight microchecking and no loss of adhesion.
- b. Accelerated Weathering Test: Withstand a weathering test for a minimum of 2000 hours in accordance with ASTM G 23, Method 1 without cracking, peeling, blistering, loss of adhesion of the protective coating, or corrosion of the base metal. Protective coating that can be readily removed from the base metal with a penknife blade or similar instrument shall be considered to indicate loss of adhesion.
- c. Chalking Resistance: After the 2000-hour weatherometer test, exterior coating shall not chalk greater than No. 8 rating when measured in accordance with ASTM D 4214 test procedures.
- d. Color Change Test:

After the 2000 -hour weatherometer test, exterior coating color change shall not exceed 2 NBS units when measured in accordance with ASTM D 2244 test procedure.

- e. Salt Spray Test: Withstand a salt spray test for a minimum of 1000 hours in accordance with ASTM B 117, including the scribe requirement in the test. Immediately upon removal of the panel from the test, the coating shall receive a rating of 10, no blisters in field as determined by ASTM D 714; and an average rating of 7, 1/16 inch failure at scribe, as determined by ASTM D 1654. Rating Schedule No. 1.
- f. Abrasion Resistance Test for Color Coating: When subjected to the falling sand test in accordance with ASTM D 968, coating system shall withstand a minimum of 100 liters of sand per mil thickness before appearance of base metal.
- g. Humidity Test: When subjected to a humidity cabinet test in accordance with ASTM D 2247 for 1000 hours, a scored panel shall show no signs of blistering, cracking, creepage, or corrosion.
- h. Gloss Test: The gloss of the finish shall be 30 plus or minus 5 at an angle of 60 degrees, when measured in accordance with ASTM D 523.

1.7 WARRANTY

Furnish manufacturer's no-dollar-limit materials and workmanship warranty for the roofing system. The warranty period shall be not less than 20 years from the date of Government acceptance of the work. The warranty shall be issued directly to the Government. The warranty shall provide that if within the warranty period the metal roofing system becomes non-watertight or shows evidence of corrosion, perforation, rupture or excess weathering due to deterioration of the roofing system resulting from

defective materials or installed workmanship the repair or replacement of the defective materials and correction of the defective workmanship shall be the responsibility of the roofing system manufacturer. Repairs that become necessary because of defective materials and workmanship while roofing is under warranty shall be performed within 7 days after notification, unless additional time is approved by the Contracting Officer. Failure to perform repairs within the specified period of time will constitute grounds for having the repairs performed by others and the cost billed to the manufacturer. The Contractor shall also provide a 2 year contractor installation warranty.

1.8 DELIVERY, STORAGE AND HANDLING

Deliver, store, and handle preformed panels, bulk roofing products and other manufactured items in a manner to prevent damage or deformation.

1.8.1 Delivery

Provide adequate packaging to protect materials during shipment. Crated materials shall not be uncrated until ready for use, except for inspection. Immediately upon arrival of materials at the jobsite, inspect materials for damage, dampness, and staining. Damaged or permanently stained materials that cannot be restored to like-new condition shall be replaced with satisfactory material. If materials are wet, remove the moisture and re-stack and protect the panels until used.

1.8.2 Storage

Stack materials on platforms or pallets and cover with tarpaulins or other suitable weathertight covering which prevents water trapping or condensation. Store materials so that water which might have accumulated during transit or storage will drain off. Do not store the panels in contact with materials that might cause staining, such as mud, lime, cement, fresh concrete or chemicals. Protect stored panels from wind damage.

1.8.3 Handling

Handle material carefully to avoid damage to surfaces, edges and ends.

PART 2 PRODUCTS

2.1 ROOFING PANELS

Panels shall have interlocking ribs for securing adjacent sheets. System for securing the roof covering to structural framing members shall be concealed clip fastening system with no fasteners penetrating the panels except at the ridge or eave, rakes, penetrations, and end laps. Backing plates and ends of panels at end laps shall be predrilled or prepunched; factory prepare ends of panels to be lapped by trimming part of seam, die-setting or swaging ends of panels. Length of sheets shall be sufficient to cover the entire length of any unbroken roof slope when such slope is 30 feet or less. When length of run exceeds 30 feet, each sheet in the run shall extend over two or more spans. Sheets longer than 30 feet may be furnished if approved by the Contracting Officer. Width of sheets shall provide not less than 12 inches of coverage in place. Height of corrugations of adjacent roof sheets shall be not less than 2.25 inches (nominal). Make provisions for expansion and contraction at either ridge or eave, consistent with the type of system to be used. Panels from coil

stock shall be formed without warping, waviness or ripples not part of the panel profile and shall be free of damage to the finish coating system.

2.1.1 Material

Zinc-coated steel conforming to ASTM A 653/A 653M, G90 coating designation or aluminum-zinc alloy coated steel conforming to ASTM A 792/A 792M, AZ 55 coating. Minimum thickness to be 0.030 inch (22 gage). Prior to shipment, treat mill finish panels with a passivating chemical and oil to inhibit the formation of oxide corrosion products. Dry, retreat, and re-oil panels that have become wet during shipment or storage but have not started to oxidize.

2.1.2 Texture

Smooth.

2.1.3 Finish

Factory color finish.

2.1.3.1 Factory Color Finish

Provide factory applied, thermally cured coating to exterior and interior of metal roof and wall panels and metal accessories. Color shall be as specified in Section 09915 "Color Schedule". Provide exterior finish top coat of 70 percent resin polyvinylidene fluoride with not less than 0.8 mil dry film thickness. Provide exterior primer standard with panel manufacturer with not less than 0.8 mil dry film thickness. Interior finish shall consist of the same coating and dry film thickness as the exterior coating. Provide exterior and interior coating meeting test requirements specified below. Tests shall have been performed on same factory finish and thickness provided. Provide clear factory edge coating on all factory cut or unfinished edges.

2.2 INTERMEDIATE SUPPORTS

Fabricate panel subgirts, subpurlins, T-bars, Z-bars and tracks from galvanized steel conforming to ASTM A 653/A 653M, G90, Grade D (16 gage and heavier), Grade A (18 gage and lighter); or steel conforming to ASTM A 36/A 36M, ASTM A 570/A 570M , or ASTM A 607 prime painted with zinc-rich primer. Size, shape, thickness and capacity as required to meet the load, insulation thickness and deflection criteria specified.

2.3 ATTACHMENT CLIPS

Fabricate clips from ASTM A 366/A 366M, ASTM A 570/A 570M, or ASTM A 607 steel hot-dip galvanized in accordance with ASTM A 653/A 653M, G 90, or Series 300 stainless steel. Size, shape, thickness and capacity as required to meet the load, insulation thickness and deflection criteria specified.

2.4 ACCESSORIES

Sheet metal flashings, gutters, downspouts, trim, moldings, closure strips, pre-formed crickets, caps, equipment curbs, and other similar sheet metal accessories used in conjunction with preformed metal panels shall be of the same material as used for the panels. Provide metal accessories with a factory color finish to match the roofing panels, except that such items

which will be concealed after installation may be provided without the finish if they are stainless steel. Metal shall be of a thickness not less than that used for the panels. Thermal spacer blocks and other thermal barriers at concealed clip fasteners shall be as recommended by the manufacturer except that wood spacer blocks are not allowed.

2.4.1 Closures

2.4.1.1 Rib Closures

Corrosion resisting steel, closed-cell or solid-cell synthetic rubber, neoprene or polyvinyl chloride pre-molded to match configuration of rib opening. Material for closures shall not absorb water.

2.4.1.2 Ridge Closures

Metal-clad foam or metal closure with foam secondary closure matching panel configuration for installation on surface of roof panel between panel ribs at ridge and headwall roof panel flashing conditions and terminations. Foam material shall not absorb water.

2.4.2 Fasteners

Zinc-coated steel, corrosion resisting steel, zinc cast head, or nylon capped steel, type and size specified below or as otherwise approved for the applicable requirements. Design the fastening system to withstand the design loads specified. Exposed fasteners shall be gasketed or have gasketed washers on the exterior side of the covering to waterproof the penetration. Washer material shall be compatible with the covering; have a minimum diameter of 3/8 inch for structural connections; and gasketed portion of fasteners or washers shall be neoprene or other equally durable elastomeric material approximately 1/8 inch thick.

2.4.2.1 Screws

Not smaller than No. 14 diameter if self-tapping type and not smaller than No. 12 diameter if self-drilling and self-tapping.

2.4.2.2 Bolts

Not smaller than 1/4 inch diameter, shouldered or plain shank as required, with proper nuts.

2.4.2.3 Automatic End-Welded Studs

Automatic end-welded studs shall be shouldered type with a shank diameter of not smaller than 3/16 inch and cap or nut for holding covering against the shoulder.

2.4.2.4 Explosive Driven Fasteners

Fasteners for use with explosive actuated tools shall have a shank diameter of not smaller than 0.145 inch with a shank length of not smaller than 1/2 inch for fastening to steel and not smaller than one inch for fastening to concrete.

2.4.2.5 Rivets

Blind rivets shall be stainless steel with 1/8 inch nominal diameter shank.

Rivets shall be threaded stem type if used for other than the fastening of trim. Rivets with hollow stems shall have closed ends.

2.4.3 Sealants

Elastomeric type containing no oil or asphalt. Exposed sealant shall cure to a rubberlike consistency. Concealed sealant shall be the non-hardening type. Seam sealant shall be factory-applied, non-skinning, non-drying, and shall conform to the roofing manufacturer's recommendations. Silicone-based sealants shall not be used in contact with finished metal panels and components unless approved otherwise by the Contracting Officer.

2.4.4 GASKETS AND INSULATING COMPOUNDS

Nonabsorptive and suitable for insulating contact points of incompatible materials. Insulating compounds shall be nonrunning after drying.

2.5 THERMAL INSULATION

Flexible blanket, rigid, or semi-rigid faced with a flexible vapor retarder. Insulation and facing shall have a flame-spread rating of 50 or less in accordance with ASTM E 84. Vapor retarder facing shall have a permeance rating of 0.05 perm or less. Provide a thermal resistance "R" value of 25 or more. Exposed insulation shall have a white nondusting and nonshedding finish. Facings and finishes shall be factory-applied.

2.6 LINER PANELS

Fabricate liner panels of the same material as roof panels, and formed or patterned to prevent waviness and distortion. Liner panels shall have a factory applied, one mil thick minimum painted coating on the inside face and a prime coat on the liner side.

PART 3 EXECUTION

3.1 EXAMINATION

Examine surfaces to receive standing seam metal roofing and flashing. Ensure that surfaces are plumb and true, clean, even, smooth, as dry and free from defects and projections which might affect the installation.

3.2 PROTECTION FROM CONTACT WITH DISSIMILAR MATERIALS

3.2.1 Cementitious Materials

Paint metal surfaces which will be in contact with mortar, concrete, or other masonry materials with one coat of alkali-resistant coating such as heavy-bodied bituminous paint.

3.2.2 Contact with Wood

Where metal will be in contact with wood or other absorbent material subject to wetting, seal joints with sealing compound and apply one coat of heavy-bodied bituminous paint.

3.3 INSTALLATION

Install in accordance with the approved manufacturer's erection instructions, shop drawings, and diagrams. Panels shall be in full and

firm contact with attachment clips. Where prefinished panels are cut in the field, or where any of the factory applied coverings or coatings are abraded or damaged in handling or installation, they shall, after necessary repairs have been made with material of the same color as the weather coating, be approved before being installed. Seal completely openings through panels. Correct defects or errors in the materials. Replace materials which cannot be corrected in an approved manner with nondefective materials. Provide molded closure strips where indicated and where necessary to provide weathertight construction. Use shims as required to ensure attachment clip line is true. Use a spacing gage at each row of panels to ensure that panel width is not stretched or shortened.

3.3.1 Roof Panels

Apply roofing panels with the standing seams parallel to the slope of the roof. Provide roofing panels in longest practical lengths from ridge to eaves (top to eaves on shed roofs), with no transverse joints except at the junction of ventilators, curbs, skylights, chimneys, and similar openings. Install flashing to assure positive water drainage away from roof penetrations. Locate panel end laps such that fasteners do not engage supports or otherwise restrain the longitudinal thermal movement of panels.

Form field-formed seam type system seams in the field with an automatic mechanical seamer approved by the manufacturer. Attach panels to the structure with concealed clips incorporated into panel seams. Clip attachment shall allow roof to move independently of the structure, except at fixed points as indicated.

3.3.2 Insulation Installation

Insulation shall be installed between covering and supporting members to present a neat appearance. Fold and staple and tape seams unless approved otherwise by the Contracting Officer.

3.3.2.1 Rigid or Semi-Rigid Insulation

Install in areas where insulation is exposed to view. Fasten securely without loose joints or unsightly sags.

3.3.2.2 Blanket Insulation

May be used in concealed locations. Lap facing at joints and fasten in a manner that will provide tight joints.

3.3.3 Flashings

Provide flashing, related closures and accessories as indicated and as necessary to provide a weathertight installation. Install flashing to ensure positive water drainage away from roof penetrations. Flash and seal the roof at the ridge, eaves and rakes, and projections through the roof. Place closure strips, flashing, and sealing material in an approved manner that will assure complete weathertightness. Details of installation which are not indicated shall be in accordance with the SMACNA Arch. Manual, panel manufacturer's approved printed instructions and details, or the approved shop drawings. Allow for expansion and contraction of flashing.

3.3.4 Flashing Fasteners

Fastener spacings shall be in accordance with the panel manufacturer's recommendations and as necessary to withstand the design loads indicated.

Install fasteners in roof valleys as recommended by the manufacturer of the panels. Install fasteners in straight lines within a tolerance of 1/2 inch in the length of a bay. Drive exposed penetrating type fasteners normal to the surface and to a uniform depth to seat gasketed washers properly and drive so as not to damage factory applied coating. Exercise extreme care in drilling pilot holes for fastenings to keep drills perpendicular and centered. Do not drill through sealant tape. After drilling, remove metal filings and burrs from holes prior to installing fasteners and washers. Torque used in applying fasteners shall not exceed that recommended by the manufacturer. Remove panels deformed or otherwise damaged by over-torqued fastenings, and provide new panels.

3.3.5 Rib and Ridge Closure/Closure Strips

Set closure/closure strips in joint sealant material and apply sealant to mating surfaces prior to adding panel.

3.4 PROTECTION OF APPLIED ROOFING

Do not permit storing, walking, wheeling, and trucking directly on applied roofing materials. Provide temporary walkways, runways, and platforms of smooth clean boards or planks as necessary to avoid damage to applied roofing materials, and to distribute weight to conform to indicated live load limits of roof construction.

3.5 CLEANING

Clean exposed sheet metal work at completion of installation. Remove metal shavings, filings, nails, bolts, and wires from roofs. Remove grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces shall be free of dents, creases, waves, scratch marks, solder or weld marks and damage to the finish coating.

3.6 MANUFACTURER'S FIELD INSPECTION

Manufacturer's technical representative shall visit the site as necessary during the installation process to assure panels, flashings, and other components are being installed in a satisfactory manner. Manufacturer's technical representative shall perform a field inspection during the first 20 squares of roof panel installation and at substantial completion prior to issuance of warranty, as a minimum, and as otherwise requested by the Contracting Officer. Additional inspections shall not exceed one for 100 squares of total roof area with the exception that follow-up inspections of previously noted deficiencies or application errors shall be performed as requested by the Contracting Officer. Each inspection visit shall include a review of the entire installation to date. After each inspection, a report, signed by the manufacturer's technical representative, shall be submitted to the Contracting Officer noting the overall quality of work, deficiencies and any other concerns, and recommended corrective actions in detail. Notify Contracting Officer a minimum of 2 working days prior to site visit by manufacturer's technical representative.

3.7 COMPLETED WORK

Completed work shall be plumb and true without oil canning, dents, ripples, abrasion, rust, staining, or other damage detrimental to the performance or aesthetics of the completed roof assembly.

-- End of Section --

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION APG AMENDMENTS						CONTRACTOR											
ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH	GOVT CLASSIFICATION REV WR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION		APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
						SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07611N	SD-02 Shop Drawings														
			Roofing	1.2.5	G AE												
			SD-03 Product Data														
			Roofing panels	2.1	G AE												
			Attachment clips	2.3													
			Closures	2.4.1													
			Accessories	2.4													
			Fasteners	2.4.2													
			Sealants	2.4.3													
			Insulation	2.5													
			warranty	1.7	G AE												
			SD-04 Samples														
			panel	2.1													
			Accessories	2.4													
			Sealants	2.4.3													
			Intermediate Support	2.2													
			SD-05 Design Data														
			Design calculations	1.5													
			SD-06 Test Reports														
			Field Inspection	3.6													
			Structural performance	1.3.3													
			Finish	1.6.6													
			SD-07 Certificates														
			Manufacturer's Technical Representative	1.6.3													
			Installer's Qualifications	1.6.4													

